
Fukushima Nuclear Accident Interim Report:

**Effects of the Earthquake and Tsunami on the
Fukushima Daiichi and Daini Nuclear Power Stations,
especially on electric and I&C systems and equipments**

July 27, 2011

@IEEE Nuclear Power Engineering Committee

Akira Kawano

Tokyo Electric Power Company


What I will present

- 1 . What occurred at Fukushima Daiichi (1F) & Daini (2F) in Japan ?
 - Earthquake - Tsunami
- 2 . What made the difference between 1F and 2F ?
 - Electric equipment - Instrumentation & Control
 - Transmission lines
3. How we responded ?
 - What difficulties existed
 - What were effectively utilized
4. Current status and Roadmap
5. Summary
6. References
 - Damage status of electric equipments - Restoration process
 - Measures to ensure safe shutdown - Chronology

1 . What occurred at Fukushima Daiichi (1F) & Daini (2F) in Japan ?


- Earthquake
- Tsunami

Overview of Fukushima Daiichi (1 F) NPS



Location	Unit	In operation since	Plant type	Power Output (MW)	Main Contractor	Pre-earthquake status
Ohkuma	1	1971.3	BWR-3	460	GE	Operating
	2	1974.7	BWR-4	784	GE/Toshiba	Operating
	3	1976.3	BWR-4	784	Toshiba	Operating
	4	1978.10	BWR-4	784	Hitachi	Shutdown for maintenance
Futaba	5	1978.4	BWR-4	784	Toshiba	Shutdown for maintenance
	6	1979.10	BWR-5	1100	GE/Toshiba	Shutdown for maintenance

Overview of Fukushima Daini (2 F) NPS




Unit 4
Unit 3
Unit 2
Unit 1

Location	Unit	In operation since	Plant type	Power Output (MW)	Main Contractor	Pre-earthquake status
Naraha	1	1982.4	BWR-5	1100	Toshiba	Operating
	2	1984.2	BWR-5	1100	Hitachi	Operating
Tomioka	3	1985.6	BWR-5	1100	Toshiba	Operating
	4	1987.8	BWR-5	1100	Hitachi	Operating

Tohoku Pacific Ocean Earthquake

- **Time:** 2:46 pm on Fri, March 11, 2011.
- **Place:** Offshore Sanriku coast (northern latitude of 38 degrees, east longitude of 142.9), 24km in depth, Magnitude 9.0
- **Intensity:** **Level 7** at Kurihara in Miyagi Miyagi prefecture
Upper 6 at Naraha, Tomioka, Okuma, and Futaba in Fukushima pref.
Lower 6 at Ishinomaki and Onagawa in Miyagi pref., Tokai in Ibaraki pref.
Lower 5 at Kariwa in Niigata pref.
Level 4 at Rokkasho, Higashidori, Mutsu and Ohma in Aomori pref., Kashiwazaki in Niigata pref.



Safe shutdown: Unit 1-3 of 1F and Unit 1-4 of 2F were **successfully shut down by control rods insertion after the earthquake.**

Scram set point by acceleration @ basement of reactor building: Horizontal=135-150 gal, Vertical=100gal

Damages by the earthquake: not fully inspected (Ex.inside PCV) but **safety related systems might not be damaged significantly.**

No functional failure of safety related systems was found through plant walk down @2F, that was also proven by the fact that plant parameters were within ordinary range and the dynamic function of equipments was intact.

Seismic Observed Data

Comparison between Basic Earthquake Ground Motion and the record of intensity

Observation Point (The lowest basement of reactor buildings)		Observed data (*interim)			Maximum Response Acceleration against Basic Earthquake Ground Motion (Gal)		
		Maximum Response Acceleration (Gal)					
		Horizontal (N-S)	Horizontal (E-W)	Vertical	Horizontal (N-S)	Horizontal (E-W)	Vertical
Fukushima Daiichi	Unit 1	460※2	447※2	258※2	487	489	412
	Unit 2	348※2	550※2	302※2	441	438	420
	Unit 3	322※2	507※2	231※2	449	441	429
	Unit 4	281※2	319※2	200※2	447	445	422
	Unit 5	311※2	548※2	256※2	452	452	427
	Unit 6	298※2	444※2	244	445	448	415
Fukushima Daini	Unit 1	254	230※2	305	434	434	512
	Unit 2	243	196※2	232※2	428	429	504
	Unit 3	277※2	216※2	208※2	428	430	504
	Unit 4	210※2	205※2	288※2	415	415	504

*1: The data above is interim and is subject to change.

*2: The recording time was about 130-150 seconds

Fukushima
Daiichi

Almost whole area was flooded

Point 1

Point 2

Fukushima Daiichi NPS after tsunami
(Blue color: flooded area)

Tsunami Attack to Fukushima Daiichi NPS (Point1)



Tsunami Attack to Fukushima Daiichi NPS (Point2)



Pictures before / after Tsunami @1F




Trees were stripped away



Damages by Tsunami @ 1F (1/3)

Heavy oil tank floated





Large size crane moved



Damages by Tsunami @ 1F (2/3)



Damages by Tsunami @ 1F (3/3)



① Area on the opposite side of coast was also flooded



② Soil and sand brought by tsunami

Damages by earthquake @ Shinfukushima substation

- About 10 km away from both 1F and 2F site
- Important switchgear station from which electricity of 1F & 2F is transmitted to Tokyo area





500kV Disconnector



275kV Circuit Breaker

Damage status of transmission line

Yonomori line No.27 Iron tower collapse



Collapse of filled soil & sand (viewpoint 1)




Transmission tower collapse (viewpoint 2)



2 . What made the difference between 1F and 2F ?


- Electric equipment
- Instrumentation & Control
- Transmission lines

Flooded & Run up Area @ 1F v.s. 2F




Tsunami Height @1F v.s. 2F

- The new design basis Tsunami height for 1F & 2F were evaluated based on the [JSCE Tsunami assessment methodology](#). (1F: O.P.+5.7m, 2 F: O.P.+5.2m)
- The [countermeasures](#) were [implemented](#) at both NPSs, such as pump motor elevation raised @1F and openings sealed @2F, that were all equivalent from the viewpoint of resistance against Tsunami hazard.
- The 15m class Tsunami caused by M9.0 class earthquake that accidentally attacked 1F was [far beyond design basis](#) and [whatever evaluation and whatever countermeasures did not matter](#) at this time.




A tsunami about 14m high swept over the entire site of Fukushima Daiichi, with flood waters reaching depths of 4 to 5m


Fukushima Daiichi




Fukushima Daiichi Nuclear Power Station Flooding height and depth, etc.
 (Further investigations are currently underway)

Flooding caused by the Tsunami






Differences in Tsunami that hit 1F and 2F



Power supply of Unit 1-4 @ 1F before earthquake


Unit 1-3 in operation, Unit 4 during outage



Power supply of Unit 1-4 @ 1F after Tsunami

Okuma Line 1L, 2L: Receiving circuit breaker damaged in earthquake
 Okuma Line 3L: Renovation work in progress
 Okuma Line 4L: Circuit breaker shutdown by protection relay activation


✗ Shutdown by earthquake
 ✗ Shutdown by Tsunami




The DG lost the function due to either "M/C failure," "loss of sea water system," or "DG main unit failure."

Power supply of Unit 5/6 @ 1F before earthquake


Unit 5/6 during outage



Power supply of Unit 5/6 @ 1F after Tsunami




Outline of water injection systems @1F3 (1/2)



Outline of water injection systems @1F3 (2/2)


After Tsunami



2F Offsite Power was secured after the Tsunami

Offsite Power

- One 500 kV line was available.
- 66 kV lines were outage because of scheduled maintenance and substation trouble but recovered.
- Many power centers and motors were damaged because of the flooding.




What made the difference between 1F and 2F

- **Tsunami height**
 - 1F: **14-15m** in average
 - 2F: **6.5-7m** in average, except on the southern side of unit 1 (run-up height was 14-15m)
- **Offsite Power**
 - 1F: **all lost**
 - 2F: one of the **offsite power lines survived** and the **stepdown transformer** between 500kv/66kv existed
- **Location and elevation of M/C switchgear and D/G**
 - 1F1-5 D/G & M/C: **T/B B1F flooded**
 - 1F6 D/G & M/C: **R/B B1F & 1F survived but sea water pump-motor flooded** (loss of cooling function)
 - 1F2-4 air-cooled D/G: **Shared pool 1F, M/C: B1F flooded**
 - 1F6 **air-cooled D/G: independent building 1F survived, M/C: R/B B1F survived**
 - 2F D/G & M/C: **R/B B1F & B2F**
 - D/G & M/C of Unit 1: **damaged by flooding**
 - D/G 3B, 3H and 4H: **in stand-by condition**
 - the other D/Gs: **out of function because of loss of cooling function (pump-motor flooding)**

3. How we responded ?

- What difficulties existed
- What were effectively utilized

Progress made by each plant towards cold shutdown (outline)



Status of 1F 1-3 immediately after the tsunami (1)

- Fallen into the Station Black Out (SBO):
 - All safety and non-safety systems driven by electricity were unavailable.
 - No lights in the control rooms, R/Bs, T/Bs, etc.
 - No important instrumentations for Unit 1 &2 due to loss of AC power sources and DC 125V batteries; the reactor water level/ pressure, drywell pressure, wet-well (S/C) pressure, etc. ; **Operators were totally blind!**
 - The instrumentation of Unit 3 was available immediately after the tsunami but only lasted for about 30hours because the DC 125V battery charger was flooded.
- No communication media between the Emergency Response Room and workers at the field: only one wired telephone was available between the ERR and each control room.

Status of 1F 1-3 immediately after the tsunami (2)

- The sea water systems were totally destroyed: **no ultimate heat sink**
- Status of cooling and flooding of the reactors were as follows:
 - Operation of the **isolation condenser** of Unit 1 was **unclear**.
 - The **RCIC** system of **Unit 3** tripped after about **21 hours** since the tsunami. Then the **HPCI** system was activated but worked only for about **14 hours**.
 - The **RCIC** system of **Unit 2** worked for about **three days** after the tsunami but the actual status could not be confirmed at the control room.

What 1F site focused on during March 11-15





- Establishing an **alternative method to inject water into the reactor pressure vessel (RPV)**
- **Venting** of the primary containment vessel (PCV)
- Recovery of the most important **instrumentations**:
 - reactor water level
 - reactor pressure
 - drywell pressure
 - wet-well (suppression chamber: S/C) pressure
- Recovery of the **lights in the control rooms** and other power supply sources

What were available for the recovery work after the tsunami?

There were only the following limited number of devices and tools available !

- Fire Engines: only a few people knew how to operate them.
- Flashlights
- Cable
- Tools (screwdrivers, etc.)
- Batteries taken from cars
- Engine driven Generators*
- Engine driven Air Compressors*

*They were in the warehouses of the affiliated companies and difficult to find.



Human Resource Issues after the Tsunami @1F


- After the tsunami, approximately **400 people** (about 130 for operation, about 270 for maintenance) were available for the recovery process.
- The number of the **operations personnel was totally insufficient** for the recovery operation of six units.
- About 70 TEPCO employees (maintenance) and about 40 people from affiliated companies were engaged in the initial field work to recover Unit 1-3; most of the work was recovery of instrumentations and power supply.
- Number of **electric and I&C maintenance personnel was also insufficient**.
- **High radiation dose** made the above human resource problem more serious.

Alternative water injection into the reactors @1F

1. Tried to inject fresh water using the diesel driven fire protection pump (DDFP): failed.
 - Unit 1: mechanical problem of the DDFP
 - Unit 2: the DDFP was flooded
 - Unit 3: the RPV pressure was too high
 2. Injection of fresh water from underground water tank (16units/site×40m³/site) using the fire engine pumps : succeeded but did not last for long time due to insufficient water supply.
 3. Injection of sea water using the fire engine pump.
 - Hurdles for the work:
 - Suspensions due to aftershocks and tsunami alarms
 - Damages of the fresh water lines due to the earthquake
 - Debris and damages of the gates caused by the tsunami
 - Hydrogen explosions (rubble, damage of fire engines and other devices, injury of field workers and fear of another explosion)
-
- TEPCO TOKYO ELECTRIC POWER COMPANY
- No lights. Problem with the PHS telephone and radio communication
- All Rights Reserved ©2011 The Tokyo Electric Power Company, Inc.

Venting of the PCV @1F

It was extremely difficult to achieve the venting line without supply of the electricity and instrumentation air. High radiation dose in R/B also impeded the work.



Initial recovery of instrumentations and power supply @1F

- Used **batteries taken from cars** for recovery of important instrumentations.
- Put **Engine-Generators** to provide power for the **control room lightings**.
- Tried to connect a **power supply cart** to **P/C 2C** with temporary cable. The hydrogen explosion of Unit 1 caused damage of the temporary cable.
- Hurdles for the work:
 - **Darkness** and **suspensions due to aftershocks**, tsunami alarms,
 - Puddles, openings of manholes, debris and other obstacles caused by the tsunami,
 - **Influence of the hydrogen explosions**

Batteries brought into the control room



Image of a power supply cart



Factors disturbing the recovery work (outside the buildings) @1F

- The initial recovery work after the tsunami was dangerous due to aftershocks , openings of manholes, cracks and holes on the roads. Especially work during night was in complete darkness and very dangerous.
- Many obstacles such as rubble and damaged cars disturbed the access to equip. & comp..



Cracks and holes on the roads: dangerous even for walking, especially during night.

Obstacles on access routes: needed not to pass on the fire protection hose. After the explosions, damaged fire engines, rubble disturbed the access.



Setting up a temporary power source (1):

Destroy the shutter of the delivery entrance by a construction machine.

Setting up a temporary power source (2):

Laying of cable was done by man power



Factors disturbing the recovery work (inside the buildings) @1F

- Activities were done in complete darkness due to lack of power sources.
- In some places, radiation dose level was very high.



Work in complete darkness

In the service building. Many scattered objects were also on the floor.

Temporary power supply

Connect temporary batteries to recover instrumentations.



Supervising (1)

Check indicated values only with a flashlight in complete darkness

Supervising (2)


Supervising at a deputy supervisor's desk wearing a full face mask in complete darkness




Efforts to recover the status of 1F5

- Unit 5 also lost the all AC power supply (Only one train of the DC125V battery was available: Temporary AC power had been supplied to the charger before the battery was exhausted).
- Status of Unit 5 was just after the RPV leak test: the reactor pressure and temperature were certainly high.
- The reactor temperature of Unit 5&6 once exceeded 100°C.
- Key success stories:
 - Prompt supply of power from DG 6B to selected components of Unit 5 by directly connecting with temporary cables,
 - Prompt acquisition and utilization of general industrial grade underwater pumps as an alternative of the RHRS pumps.
- Information exchange with Fukushima Daini NPS and supports from Kashiwazaki Kariwa NPS were very useful and helpful during the recovery process.

Power Supply from 1F6 to 1F5




Alternative RHRs pump for 1F5




* The above figure shows just an illustration of the RHR system. In the actual unit, there are

Temporary Power Supply and Motor Replacement @2F


About 9 km of temporary cables were laid and motors were replaced.



1F House Power Restoration Outline Diagram (End of March)



1F House Power Restoration Outline Diagram (Mid-May)



4 . Current Status and Roadmap

Plant Parameters (Fukushima Daiichi)

as of July 20th at 6:00

RPV Pressure [MPa-g]

Unit 1	Unit 2	Unit 3
0.030	0.027	-0.106

RPV Temp [°C]


Unit 1	Unit 2	Unit 3
110.6 (Feedwater Nozzle)	126.0 (bottom of RPV)	135.4 (Feedwater Nozzle)

Reactor water level [mm]

Unit 1	Unit 2	Unit 3
Below the range	-2,150	-2,300

Drywell pressure [MPa-abs]

Unit 1	Unit 2	Unit 3
0.1378	0.130	0.1016





*We are judging the plant status by utilizing data obtained from multiple instruments including their changing trend in a comprehensive manner considering that some of them possibly are showing inaccurate data due to the irregular condition for use



Pressure conversion: Gauge pressure (MPa-g)=absolute pressure (MPa-abs)-atmospheric pressure(0.1013Mpa)

TOKYO ELECTRIC POWER COMPANY



Plant Parameters (Fukushima Daiichi RPV temperature)



↑Unit1

↓Unit2

Unit3↓



Evacuation

➤ The government took measures such as taking shelters or evacuation as follows based on the reports from Fukushima Daiichi & Daini.

- **Fri, 11 March**

- 14:46 The earthquake occurred
- 19:03 Emergency Declaration by the Gov't (Daiichi)
- 21:23 3 km radius evacuation (Daiichi)
- 10 km radius taking shelter (Daiichi)

- **Sat, 12 March**

- 5:44 10 km radius evacuation (Daiichi)
- 7:45 3 km radius evacuation (Daini)
- 10 km radius taking shelter (Daini)
- 17:39 10 km radius evacuation (Daini)
- 18:25 20 km radius evacuation (Daiichi)

- **Tue, 15 March**

- 11:00 20-30 km radius taking shelter (Daiichi)

- **Thu, 21 April**


- 11:00 20 km radius designated as "Restricted Area" (Daiichi)

- **Fri, 22 April**

- 9:44 20-30 km radius taking shelter has been lifted (Daiichi)
- Establishment of "Deliberate Evacuation Area" and "Evacuation Prepared Area in Case of Emergency"

- **Thu, 16 June**

- PM Establishment of "Specific Locations Recommended for Evacuation"




Source: NISA website

Monitoring Data (at Site Boundary of Fukushima Daiichi)


➤ Monitoring data at the site boundary of Fukushima Daiichi shows continuous decrease at each monitoring post.

air dose rate measured at on-site monitoring posts

: $\mu\text{Sv/h}$ as of 9:00 am on July 12th, 2011




Dose Rate Trend at the Site Boundary of Fukushima Daiichi




Schematic Diagram of Current Water Supply System


as of July 7th



Outline of Water Treatment Facility System (Highly Contaminated Water)



Water Flow of Overall Water Treatment Facility



Current Status of Roadmap towards Restoration from the Accident at Fukushima Daiichi Nuclear Power Station, TEPCO” (Revised on July 19th)

Red colored: newly added to the previous version, ☆: already reported to the government

Issues	As of April 17	Step 1 (around 3 months)	Step 2 (around 3 to 6 months after achieving Step1) current status (as of July 17)	Mid-term issues (around 3 years)	
I. Cooling	(1) Reactor Fresh water Injection	Cooling by minimum injection rate (injection cooling)	Stable cooling	Cold shutdown condition	
		Consideration and preparation of reuse of accumulated water			Circulating Injection Cooling (start) ☆
(2) Spent Fuel Pool Fresh water injection	Fresh water injection	Reliability improvement in injection operation / remote-control operation *ahead of schedule	Stable cooling	More stable cooling	
		Circulation cooling system ☆ (installation of heat exchanger) *partially ahead of schedule			Remote-controlled injection operation
II. Mitigation	(3) Accumulated Water Transferring water with high radiation level	Installation of storage / processing facilities ☆	Secure storage place	Reduction of total amount of contaminated water	
		Installation of storage facilities / decontamination processing			Expansion / consideration of full-fledged processing facilities
	(4) Ground water Storing water with low radiation level	Mitigation of contamination of groundwater	Mitigate ocean contamination	Mitigation of contamination in the ocean	Mitigation of contamination in the ocean
		Consideration of method of shielding wall of groundwater			
(5) Atmosphere / Soil	Dispersion of inhibitor	Removal of debris	Mitigate scattering	Mitigate scattering (continued)	
					Removal of debris (top of Unit 3&4 R/B)
				Start of installation work of reactor building container	


Current Status of Roadmap towards Restoration from the Accident at Fukushima Daiichi Nuclear Power Station, TEPCO” (Revised on July 19th)

Red outline: newly added to the previous version, ☆: already reported to the government

Issues		As of April 17	Step 1 (around 3 months)	Step 2 (around 3 to 6 months after achieving Step1) current status (as of July 17)	Mid-term issues (around 3 years)
III. Monitoring/Decontamination/Measurement, Reduction and Announcement	(㊟) Measurement, Reduction and Announcement		Expansion, enhancement and announcement of radiation dose monitoring in and out of the power station	Start of full-fledged decontamination	Continuous environmental monitoring Continuous decontamination
IV. Countermeasures against aftershocks, etc	(ㄣ) Tsunami, Reinforcement, etc		Enhancement of countermeasures against aftershocks and tsunami, preparation for various countermeasures for radiation shielding		Continue various countermeasures for radiation shielding
			(Unit 4 spent fuel pool) Installation of supporting structure ☆	Consideration / implementation of reinforcement work of each Unit	Reinforcement work of each Unit
V. Environment improvement	(㊟) Lifework environment		Improvement of workers' life / work environment		Improvement of workers' life / work environment
	(㊟) Radiation control / Medical care		Improvement of radiation control / medical system		Improvement of radiation control / medical system
Measures for Mid-term issues				Government's concept of securing safety Establishing plant operation plan based on the safety concept	Response based on the plant operation plan

Overview of Major Countermeasures in the Power Station

Red frame: deleted countermeasures, red colored: newly added countermeasures, ☆: already reported to the government



5 . Summary

Summary (1/3)

1. The accident at Fukushima Daiichi and Daini was caused by Tsunami far beyond the design basis. (No significant damage by earthquake)



- The current design of external barriers were not enough to cope with **hydrodynamic forces** of flooding and **large debris impact**.
- The current design of **safety-related electric and I&C equipment** might not be robust enough to prevent **common cause failure** by severe external flooding and their **layout, diversity and internal barriers** for separation need to be reviewed.

Summary (2/3)

2. Several implementable countermeasures/modifications that could have lessened the damage at the unforeseeable accident have been identified.



- **Mobile power vehicles** could be considered as redundant measures against extended SBO situation from the defense in depth viewpoint.
- **Emergency water injection and cooling capability**, against extended SBO situation, such as fire engines and air cylinders, should be considered.
- **Better preplanning, staging and logistics of emergency and spare equipment** would make a quicker recovery possible.
- **Greater consideration should be given to redundant communication measures** for organized actions.

Summary (3/3)

3. Without newly built Emergency Response Center, the post-accident activities could not have been carried out.



- **Measures taken after Niigata Chuetsu Oki Earthquake were effective:**
 - **Emergency response center** in robust building (Seismic isolation, Shielding, Communication, etc.)
 - **Underground water tank** (16 units/site×40 m³/site) and **Fire Engines** (3/site)
 - **Emergency Response Drills**

6. References

- Damage status of electric equipments
- Restoration process
 - Electric equipment
 - I&C
- Measures to ensure safe shutdown @2F
- Chronology

Damage Status of Unit 1 & 2 Emergency DG and Emergency High Voltage Switchboard (Immediately after the Tsunami)

	Unit 1					Unit 2				
	Equipment	Installed building	Installed floor	Possibility of use	Status	Equipment	Installed location	Installed floor	Possibility of use	Status
DG	DG 1A	T/B	B1FL	×	Submerged	DG 2A	T/B	B1FL	×	Submerged
	DG 1B	T/B	B1FL	×	Submerged	DG 2B	Shared pool	1FL	×	M/C submerged cannot be used
	-	-	-	-	-	-	-	-	-	-
(M/C) Emergency high voltage switchboard	M/C 1C	T/B	1FL	×	Water damage	M/C 2C	T/B	B1FL	×	Submerged
	M/C 1D	T/B	1FL	×	Water damage	M/C 2D	T/B	B1FL	×	Submerged
	-	-	-	-	-	M/C 2E	Shared pool	B1FL	×	Submerged

Damage Status of Unit 3 & 4 Emergency DG and Emergency High Voltage Switchboard (Immediately after the Tsunami)

	Unit 3					Unit 4				
	Equipment	Installed location	Installed floor	Possibility of use	Status	Equipment	Installed location	Installed floor	Possibility of use	Status
DG	DG 3A	T/B	B1FL	×	Submerged	DG 4A	T/B	B1FL	×	Submerged (Construction in progress)
	DG 3B	T/B	B1FL	×	Submerged	DG 4B	Shared pool	1FL	×	M/C submerged cannot be used
	-	-	-	-	-	-	-	-	-	-
(M/C) Emergency high voltage switchboard	M/C 3C	T/B	B1FL	×	Submerged	M/C 4C	T/B	B1FL	×	Submerged (Inspection in progress)
	M/C 3D	T/B	B1FL	×	Submerged	M/C 4D	T/B	B1FL	×	Submerged
	-	-	-	-	-	M/C 4E	Shared pool	B1FL	×	Submerged


Damage Status of Unit 5 & 6 Emergency DG and Emergency High Voltage Switchboard (Immediately after the Tsunami)

	Unit 5					Unit 6				
	Equipment	Installed location	Installed floor	Possibility of use	Status	Equipment	Installed location	Installed floor	Possibility of use	Status
D G	DG 5A	T/B	B1FL	×	Related equipment Water damage	DG 6A	R/B	B1FL	×	Related equipment Water damage
	DG 5B	T/B	B1FL	×	Related equipment Water damage	DG 6B	DG building	1FL	○	-
	-	-	-	-	-	HPCSD/G	R/B	B1FL	×	Related equipment Water damage
(M/C) Emergency high voltage switchboard	M/C 5C	T/B	B1FL	×	Submerged	M/C 6C	R/B	B2FL	○	-
	M/C 5D	T/B	B1FL	×	Submerged	M/C 6D	R/B	B1FL	○	-
	-	-	-	-	-	HPCS DG M/C	R/B	1FL	○	-

Fukushima Daiichi: DG System Outline

Sea water-cooled DG (10)


Unit 1 (A)(B), Unit 2 (A), Unit 3 (A)(B), Unit 4 (A), Unit 5 (A)(B), Unit 6 (A)(H)



All function was lost after the tsunami

Air-cooled DG (3)

Unit 2 (B), Unit 4 (B), Unit 6(B) Cooling water pump




Power was secured in Unit 6 (B) only

[Fukushima Daini: DG System Outline]

Sea water-cooled DG (12)

Unit 1 to Unit 4(A)(B)(H)



Power was secured in Unit 3 (B)(H) and Unit 4 (H) only

Integrity of electricity supply system after the tsunami attack

	Fukushima Daichi											Fukushima Daii									
	Unit 1		Unit 2		Unit 3		Unit 4		Unit 5		Unit 6		Unit 1		Unit 2		Unit 3		Unit 4		
	Power panel	Can/can not be used	Power panel	Can/can not be used	Power panel	Can/can not be used	Power panel	Can/can not be used	Power panel	Can/can not be used	Power panel	Can/can not be used	Power panel	Can/can not be used	Power panel	Can/can not be used	Power panel	Can/can not be used	Power panel	Can/can not be used	
Emergency DG	DG 1A	x	DG 2A	x	DG 3A	x	DG 4A	x	DG 5A	x	DG 6A	x	DG 1A	x	DG 2A	x	DG 3A	x	DG 4A	x	
	DG 1B	x	DG 2B	x	DG 3B	x	DG 4B	x	DG 5B	x	DG 6B		DG 1B	x	DG 2B	x	DG 3B		DG 4B	x	
	-	-	-	-	-	-	-	-	-	-	HPCS DG	x	DG 1H	x	DG 2H	x	DG 3H		DG 4H		
M/C	Emergency use	M/C 1C	x	M/C 2C	x	M/C 3C	x	M/C 4C	x	M/C 5C	x	M/C 6C		M/C 1C	x	M/C 2C		M/C 3C		M/C 4C	
		M/C 1D	x	M/C 2D	x	M/C 3D	x	M/C 4D	x	M/C 5D	x	M/C 6D		M/C 1D		M/C 2D		M/C 3D		M/C 4D	
		-	-	M/C 2E	x	-	-	M/C 4E	x	-	-	HPCS DG M/C		M/C 1H	x	M/C 2H		M/C 3H		M/C 4H	
	Regular use	M/C 1A	x	M/C 2A	x	M/C 3A	x	M/C 4A	x	M/C 5A	x	M/C 6A-1	x	M/C 1A-1		M/C 2A-1		M/C 3A-1		M/C 4A-1	
			M/C 6A-2	x	M/C 1A-2		M/C 2A-2		M/C 3A-2		M/C 4A-2										
		M/C 1B	x	M/C 2B	x	M/C 3B	x	M/C 4B	x	M/C 5B	x	M/C 6B-1	x	M/C 1B-1		M/C 2B-1		M/C 3B-1		M/C 4B-1	
			M/C 6B-2	x	M/C 1B-2		M/C 2B-2		M/C 3B-2		M/C 4B-2										
		M/C 1S	x	M/C 2SA	x	M/C 3SA	x	-	M/C 5SA-1	x	-	M/C 1SA-1		-	M/C 3SA-1		-	M/C 3SA-1		-	
			M/C 5SA-2	x	-	M/C 1SA-2		-	M/C 3SA-2		-	M/C 3SB-1		-	M/C 3SB-1		-	M/C 3SB-2		-	
			M/C 5SB-1	x	M/C 3SB	x	-	M/C 5SB-2	x	-	M/C 1SB-2		-	M/C 3SB-2		-	M/C 3SB-2		-		
P/C	Emergency use	P/C 1C	x	P/C 2C		P/C 3C	x	P/C 4C		P/C 5C	x	P/C 6C		P/C 1C-1	x	P/C 2C-1		P/C 3C-1		P/C 4C-1	
		P/C 1D	x	P/C 2D		P/C 3D	x	P/C 4D		P/C 5D	x	P/C 6D		P/C 1C-2	x	P/C 2C-2	x	P/C 3C-2	x	P/C 4C-2	x
		-	-	P/C 2E	x	-	-	-	-	-	-	P/C 6E		P/C 1D-1		P/C 2D-1		P/C 3D-1		P/C 4D-1	
	Regular use	P/C 1A	x	P/C 2A		P/C 3A	x	P/C 4A		P/C 5A	x	P/C 6A-1	x	P/C 1D-2	x	P/C 2D-2	x	P/C 3D-2		P/C 4D-2	x
			P/C 2A-1	x	HVAC P/C 3A		HVAC P/C 4A		P/C 5A-1		P/C 6A-2	x	P/C 1A-1		P/C 2A-1		P/C 3A-1		P/C 4A-1		
		P/C 1B	x	P/C 2B		P/C 3B	x	P/C 4B		P/C 5B	x	P/C 6B-1	x	P/C 1A-2		P/C 2A-2		P/C 3A-2		P/C 4A-2	
		-	-	-	-	HVAC P/C 3B		HVAV P/C 4B		P/C 5B-1		P/C 6B-2	x	P/C 1B-1		P/C 2B-1		P/C 3B-1		P/C 4B-1	
		P/C 1S	x	-	-	P/C 3SA	x	-	P/C 5SA	x	-	-	P/C 1B-2		P/C 2B-2		P/C 3B-2		P/C 4B-2		
		-	-	-	-	-	-	-	-	P/C 5SA-1	x	-	-	P/C 1SA		-	-	P/C 3SA		-	
		-	-	P/C 2SB	x	P/C 3SB	x	-	-	P/C 5SB	x	-	-	P/C 1SB		-	-	P/C 3SB		-	
-	-	-	-	-	-	-	-	-	-	-	-	Water intake equipment P/C	x	-	-	Water intake equipment P/C	x	-			
DC power supply	125V DC	DC125V main bus panel A	x	DC125V P/C 2A	x	DC125V main bus panel 3A		DC125V main bus panel 4A	x	DC125V P/C 5A		DC125V DIST CENTER 6A		DC125V main bus panel A		DC125V main bus panel A		DC125V main bus panel A		DC125V main bus panel A	
		DC125V main bus panel B	x	DC125V P/C 2B	x	DC125V main bus panel 3B		DC125V main bus panel 4B	x	DC125V P/C 5B		DC125V DIST CENTER 6B		DC125V main bus panel B		DC125V main bus panel B		DC125V main bus panel B		DC125V main bus panel B	
Sea water system	A	CCS A	x	RHRS A	x	RHRS A	x	RHRS A	x	RHRS A	x	RHRS A	x	RHRS A	x	RHRS A	x	RHRS A	x	RHRS A	x
	B	CCS B	x	RHRS B	x	RHRS B	x	RHRS B	x	RHRS B	x	RHRS B	x	RHRS B	x	RHRS B	x	RHRS B		RHRS B	x

Power Access/Restoration Status Immediately after 1F-1,2 Shutdown

Date	Operation and Restoration Status
March 11	Temporary MCR lighting on (Temporary small engine generator)
March 12	Power source for Unit 1 Instrument restored (Temporary small engine generator)
	Power source for Unit 1 Instrument restored (power source cart)
	Temporary small engine generator destroyed by H2 explosion
	Temporary MCR lighting on (another temporary small engine generator)
March 19	Backup transformer ~ Unit 1 & 2 temporary M/C (A) cable laid
March 20	Off-site power restored (P/C2C power received)

Power Access/Restoration Status Immediately after 1F-3,4 Shutdown

Date	Operation and Restoration Status
March 11	Temporary MCR lighting on (Temporary small engine generator)
March 13	P/C 4D restored (power source cart)
March 14	Yonomori Line 1L step-down transformer cart (66/6.9kW) connected to the Shin-Fukushima Substation
	Yonomori Line 1L ~ Okuma Line 3L connected
	Power source for Unit 1 Instrument restored (power source cart) The power source cart destroyed by H2 explosion
March 18	Unit 3 & 4 MC, Switch installation location
March 22	Off-site power restored (P/C4D power received)

Power Access/Restoration Status Immediately after 1F-6 Shutdown

Date	Operation and Restoration Status
March 11	DG6B startup (6A and 6H were shut down by the tsunami, 6B is an air-cooled type)
	SGTS(B) startup, DC125V/250V (B system) restoration
March 12	DC125V/250V (A system) restoration
March 13	MUWC(B) startup
March 19	RHR 6B startup , temporary RHRS alternative pump startup (power source cart)
	DG6A startup (March 21 shutdown)
March 20	Cold shutdown condition
March 22	Off-site power restored (M/C6C, 6D power received)
March 23	Temporary RHRS alternative pump switched to off-site power

Power Access/Restoration Status Immediately after 1F-5 Shutdown

Date	Operation and Restoration Status
March 12	DC125V/250 restoration
March 13	MUWC(A), SGTS(A) startup
March 18	Temporary RHRS alternative pump startup (power source cart)
March 19	RHR 5C startup
March 20	Cold shutdown condition
March 22	Off-site power restored (M/C6C, 6D power received)
March 23	Temporary RHRS alternative pump switched to off-site power

Recovery Process of I&C equipments @1F (1/2)

- After tsunami → Total loss of instrumentations due to loss of offsite power and DC 125V
- March 11-14: to install temporary batteries to important instrumentations, such as reactor water level, reactor pressure, D/W pressure, S/C pressure etc. (1F-1-3: March 11, 1F-5/6: March 14) and to start to obtain plant data
- March 22-25: to recover AC 120V bus for I&C (1F1: March 23, 1F2: March 25, 1F3/4: March 22)
- ~ Present: to prioritize the recovery of redundant instrumentations for their reliability and to change step by step from temporary battery to original power source

Recovery Process of I&C equipments @1F (2/2)

- May 9: to go into R/B to calibrate the D/W pressure instrument @1F1
- May 10-12: to calibrate the fuel zone reactor water level instrument @1F1
 - water level assumed as lower than -500cm of TAF
- June 3-4: to install the temporary reactor pressure and Δ pressure instrument at the test line of fuel zone reactor water level instrument @1F1, to obtain more precise data on reactor pressure and water level
- June 22-24: to install the temporary reactor pressure and Δ pressure instrument at the test line of fuel zone reactor water level instrument @1F2
 - not successful due to rapid evaporation of water inside instrumentation line by high PCV temperature

Current status of important instrumentations @1F

Parameter/unit	1F1	1F2	1F3	1F4	1F5	1F6
Reactor water level	A : ◎ B : △	A : △ B : △	A : △ B : △	N/A	○	○
Reactor pressure	A : ◎	A : ○	A : △ B : △	N/A	○	○
Reactor water temp.	Not sampled	Not sampled	Not sampled	N/A	○	○
Temperature around RPV	○	○	○	N/A	N/A	N/A
D/W pressure	◎	△	○	N/A	N/A	N/A
S/C pressure	○	×	○	N/A	N/A	N/A
CAMS rad monitor	D/W : × S/C : ○	D/W : ○ S/C : ○	D/W : ○ S/C : ○	N/A	N/A	N/A
S/C temperature	○	○	○	-	-	-

◎ : calibrated, ○ : assumed to be intact, △ : under continuous observation, × : failure

Measures to ensure Safe Shutdown @2F


- Tsunami Accident Management Guideline / Procedures and Drills
- Emergency Power Supply Capability under Tsunami SBO
 - Mobile power trucks with a total capacity of 8250 kVA for cooling system. (Required capacity: 6880 kVA)
- Emergency Water Injection and Cooling Capability under Tsunami SBO
 - Five fire engines with a total capacity of 120 m³/h at 0.85 MPa as back-up injection capability. (Required capacity: 30 m³/h at 0.7 MPa)
 - Spare air cylinders to drive AO valves for PCV venting
- Spare Motors and Bearings for Cooling Pumps
- Wheel Loader and Excavator to clear Debris
- Embankment




Chronology at Fukushima Daiichi Unit 1

Prior to earthquake

In rated power operation



Major Activities at Fukushima Daiichi Unit 1



Prior to earthquake

In rated power operation

March 11, 2011 14:46

Great East Japan Earthquake occurred, **reactor automatically scrammed**


14:47

Due to loss of offsite power, **emergency D/G started up**

14:52

Isolation condenser (IC) started up ¹

1: Cooling system for emergencies which cools steam from the reactor and returns it to the reactor.



Major Activities at Fukushima Daiichi Unit 1

March 11, 2011 15:37

Station Black Out due to tsunami strike

(Sea water systems also lost)

Loss of power to the main control room and instruments

Main control room: lighting off, monitoring instrumentation shut down, and operation panels disabled

Building interior: building interior lighting off, no power source for equipments

Building exterior: Debris and other obstacles scattered around due to the tsunami, manhole covers missing, etc.

•Most monitoring and operating functions in the main control room lost

•Tsunami debris dispersed around the unit, work environment deteriorated

•Activities restricted due to frequent aftershocks

Scram response

Deteriorating operability due to the tsunami


Preparations for water injection

Preparations for venting

Water injection started

Venting

Major Activities at Fukushima Daiichi Unit 1



Coolant injection means predetermined for use in an operation at the time of an accident cannot be used
Use of fire-fighting vehicles also evaluated as a practical operation

Rise in dose on site, deteriorating work environment, and frequent aftershocks

Major Activities at Fukushima Daiichi Unit 1

~~March 12, 2011 0:06~~

~~As D/W pressure might have exceeded 600kPa abs, **Site superintended directed preparations for PCV venting**~~

Scram response

Deteriorating operability due to the tsunami

Preparations for water injection

Preparations for venting

Water injection started

Venting

Pressure in the containment vessel increased and venting operation became unavoidable

Around 1:30 Venting operation proposed by TEPCO, and approved by the government

Preparation for venting

Confirmation of venting procedures

Confirmation of dose rate of the working environment

Confirmation of necessary working time in the building



Assessment of exposure dose to surrounding area during venting, etc.

In addition to the above, impact on residents in surrounding area was considered and the status of evacuation of residents in proximity to the station were checked

Major Activities at Fukushima Daiichi Unit 1

~ Containment Vessel Venting Operation (1) ~

- Two valves, a PCV vent valve (MO valve) and a S/C vent valve (AO valve: small) were selected as the target for manual PCV venting operation .
- Manual valve operation were planned to be conducted by 3 teams with 2 shift workers per team (one worker per team would be difficult due to the total darkness) and shift supervisors and vice-supervisors were selected to the team members.
- Equipment for the teams included fire-resistant clothing, self-contained breathing apparatus, APD, survey meter and flash light.
- At 9:03, it was confirmed that evacuation from the vicinity of south side of the NPS completed. At 9:04, the team members headed to the site for the venting operation.



Self-contained breathing apparatus

Major Activities at Fukushima Daiichi Unit 1



~ Containment Vessel Venting Operation (2) ~

- Scram response
- Deteriorating operability due to the tsunami
- Preparations for water injection
- Preparations for venting
- Water injection started
- Venting


Operation to manually open PCV vent valve (MO valve)

■ 1st team proceeded to site to operate PCV vent valve (MO valve) on the 2nd level of the R/B, and implemented operation to open the valve manually.

➡ **Operation to open PCV vent valve (MO valve) successful**



North-side double door



PCV vent valve (MO valve)

South-side double door

R/B 1st level

R/B 2nd level

Access route to PCV vent valve (MO valve)



TOKYO ELECTRIC POWER COMPANY



Major Activities at Fukushima Daiichi Unit 1

~ Containment Vessel Venting Operation (3) ~

- Scram response
- Deteriorating operability due to the tsunami
- Preparations for water injection
- Preparations for venting**
- Water injection started
- Venting

Operation to manually open S/C vent valve (AO valve) valves


- 2nd team entered the torus room (R/B B1F), but the valve was located at a direction of 180 degrees from where the team entered the torus room.
- The survey meter rose up to the limit on the way, and the team members returned.
- ➡ **Manual operation was abandoned and another means were selected**



North-side double door

Dose at the north-side double door was high, and south-bound course was selected

South-side double door



S/C vent valve (AO valve)

R/B 1st floor


Access route to S/C vent valve (AO valve)

R/B B1F



TOKYO ELECTRIC POWER CO.

Major Activities at Fukushima Daiichi Unit 1




March 12	5:46	Fire-fighting vehicle commenced injection of fresh water (water source: fire cistern)
	10:17	Containment vessel venting commenced
	14:30	D/W pressure decreased. Containment vessel venting succeeded

Without any power source and in a very poor working environment with continuing aftershocks, “venting successful” and “alternative injection of cooling water into reactor commenced”

Major Activities at Fukushima Daiichi Unit 1

~ Fresh Water and Sea Water Injection ~



March 12 14:53 80,000L (total) of **fresh water injection completed**
14:54 Site superintendent **directed sea water injection** into the reactor

[Fresh water injection]

- Fresh water injections were initially conducted using a fire cistern and the water was repeatedly injected through the fire-protection system water outlets.
- Rubbles and debris due to the earthquake and tsunami prevented fire engines from moving back and forth. Therefore a long fire hose was used to form a continuous water injection line between the fire-protection system water outlets and the fire cistern.


Line constructed and fresh water injected

[Sea water injection]

- Prior to the direction by the superintendent, preparations for injecting sea water have been conducted since the amount of fresh water in the fire cistern was limited.
- Judging from the condition of the roads and the distance between Unit 1 and the sea, it was decided not to take sea water directly from the sea, but to use a pit in front of the Unit 3 turbine building as the water source, in which sea water was accumulated due to the tsunami.
- Three fire engines were lined in a series in order to inject sea water into the reactor.

Preparation for injecting sea water undertaken at an early stage

Major Activities at Fukushima Daiichi Unit 1



March 12 **15:36** Explosion occurred.
Hoses prepared for injecting sea water were damaged.

- Evacuation from around the reactor building, rescue and transport of injured workers
- Site investigation of the impact of the explosion in order to ensure safety
- Laying out sea-water injection hoses again



19:04 **Injection of sea water started**

Chronology at Fukushima Daiichi Unit 2

	Prior to earthquake	In rated power operation
Scram response	March 11, 2011 14:46	Great East Japan Earthquake occurred
	14:47	Reactor automatically scrammed, and loss of offsite power supply caused emergency D/G start up
	15:39	RCIC manually started
	15:41	Tsunami caused station black out
Deteriorating operability due to the tsunami	17:12	Site superintendent directed considering cooling water injection using fire protection lines and vehicles
	21:02	Due to uncertainty about the water level and RCIC operating status, the authorities were informed that TAF might be reached
	22:00	Reactor water level confirmed to be TAF+3400mm, so it was judged that it would some take time to reach TAF
Preparations for water injection	March 12 2:55	RCIC was confirmed to be operating
	17:30	Site superintendent directed preparation for venting operation
Preparations for venting	March 13 10:15	Site superintendent directed for venting operation
	11:00	Construction of a venting line was completed except for a ruptured disk
	12:05	Site superintendent directed preparation for sea water injection
Water injection started	March 14 11:01	Due to explosion at Unit 3, vent valves were closed and water injection line became unusable
	19:54	Injection of sea water was commenced using fire-fighting vehicles from the fire-extinguishing system
Venting		line

Chronology at Fukushima Daiichi Unit 3

Scram response	Prior to earthquake	In rated power operation
	March 11, 2011 14:46	Great East Japan Earthquake occurred
Deteriorating operability due to the tsunami	Approx. 14:48	14:47 Reactor automatically scrammed
	15:38	Loss of offsite power supply caused emergency D/G to start up
	March 12	Tsunami caused station black out
	16:03	RCIC manually started
Preparations for water injection	11:36	RCIC tripped
	12:35	HPCI automatically started (low reactor water level)
	17:30	Site superintendent directed preparation for venting operation
Preparations for venting	March 13 2:42	HPCI tripped
		5:15 Site superintendent directed venting line to be constructed except for a ruptured disk
Water injection started		8:41 Construction of a venting line was completed except for the ruptured disk
	Approx. 9:20	Venting operation confirmed decrease in the D/W pressure
Venting		9:25 Injection of fresh water commenced using fire-fighting vehicles from fire-extinguishing line (~12:00)
		13:12 Injection of sea water commenced using fire-fighting vehicles from fire-extinguishing line
	March 14	11:01 Explosion in the reactor building (fire-fighting vehicles and hoses damaged)
	Approx. 16:30	Fire-fighting vehicles and hoses were replaced and injection of sea water recommenced

Water injection using RCIC/HPCI